



GURUGRAM UNIVERSITY

GURUGRAM (HARYANA)

(Established under Haryana Act 17 of 2017)

Construction & Maintenance

NOTICE INVITING QUOTATIONS

No. GUG/CE / 2023 / 210

Date: 17/10/2023

Sealed quotations on fixed percentage rate basis are hereby invited by the undersigned on behalf of the Vice – Chancellor of the University from the approved Co-op L&C Societies/contractors/ from 18.10.2023 to 24.10.2023 till 3:00 PM. If no Co-op L&C Societies come forward the quotations, then the same will be received by the approved PWD (B&R) / HUDA / CPWD / GUG-UST / MES / Railways / HSAMB / HPHC or any other State / Centre Govt. Deptt. / Boards / Corporations. The Quotations will be opened on the same date at the time shown above in the presence of the agencies or their authorized representatives who may like to present at the time.

Name of the work:- Civil work of Pantry in accounts branch and media branch of Gurugram University, Sec-51, Gurugram

S. No.	Description of the Items (s)	Qty.	Unit
1.	Civil work of Pantry in accounts branch and media branch of Gurugram University, Sec-51, Gurugram.	As per Annexure-A	

Conditions:

1. Conditional Quotations will be Out rightly rejected.
2. The work shall be carried out as per PWD specifications.
3. 1% / 2% T.D.S. and GST 2 % or as amended from time to time by the Govt. will be deducted from every bill of the agency.
4. Nothing shall be paid whatsoever for any loss or damages done by rains, flood or any act of God.
5. The amount of the work order can be increased or decreased as per actual requirement at site of work as desired by the Engineer-in-charge of the without any compensation.
6. If any other item not shown above will be executed, the rate will be paid approved by the competent authority.
7. Undersigned reserves the right to accept or reject any quotation without assigning any reason the thereof.
8. Co-op L&C Societies/contractors will have to deposit 2% as EMD if cost of P.O Exceed Rs 40,000.00.

CC: -


SDE/XEN

1. S.E.

ANNEXURE A

Civil work of Pantry in accounts branch and me branch of Gurugram University, Sec-51, Gurugram.

Sr. no	HSR/NS	Description of work	Qty	Unit	HSR rate	Rate to be quoted by Bidder (tax incl.)	Amount
1.	HSR 7.22	Brick work with common burnt clay non-modular bricks of class designation 7.5 in superstructure above plinth level up to floor IV level in all shapes and sizes in: 7.22.1 Cement mortar 1:4 (1 cement: 4 coarse sand)	0.71	CUM	4575.34		
2.	HSR 10.50.1	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1 :4 (1 cement : 4 coarse sand) laid and	3.09	SQM	3193.89		

		<p>jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing , curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge.10.50.1 Polished Granite stone slab jet Black, Cherry Red, Elite Brown, sqm Cat Eye or equivalent.</p>				
3.	HSR 10.58	<p>Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS : sqm 235 368 603 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1 :3</p>	14.84	SQM	635.40	

		(1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.					
4.	HSR 22.10.1. 1	Providing and fixing Stainless Steel A ISi 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required 22.10.1 Kitchen sink with drain board 22.10.1.1 510x1040 mm bowl depth 250 mm	2.0	EACH	4388.83		
5	HSR 9.57	Providing and fixing on wall face Unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring					

		conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed						
5.0 1	A	110 mm diameter. HSR 9.57.2	2.0	MTR	236.04			
5.0 2	B	75 mm diameter HSR 9.57.1	7.0	MTR	143.31			
			Total Amount HSR					
			In words _____					
			-					